

April 18, 2022

REQUEST FOR QUOTES (Amended)

TO: Qualified Contractors

FROM: Devanee Morrison
Executive Director

SUBJECT: **LHSF PROJECT NO. 090122**
Waterslide Gel Coat, Paint, and Minor Repair
Lava Hot Springs Olympic Swimming Complex
Lava Hot Springs, Idaho



Submittals will be received electronically by **Devanee Morrison, Executive Director** (devanee.morrison@lava.idaho.gov) until **May 4, 2022, at 4:00 p.m.**, for repair, caulk, paint, and gel coat of waterslides at Lava Hot Springs, Idaho.

Questions that arise because of this Request for Qualifications should be addressed to:

Devanee Morrison, Executive Director
Lava Hot Springs Foundation
430 E. Main Street
P O Box 669
Lava Hot Springs, ID 83246
(208) 589-2702
devanee.morrison@lava.idaho.gov

All contractors must carry and maintain a minimum of \$1,000,000 in professional liability insurance. Modifications to this RFQ, if any, will be posted on the Lava Hot Springs website at www.lavahotsprings.com. It is recommended that responders to this RFQ check this page prior to making their submittal. If any, the final addendum will be issued by April 15, 2022.

The Lava Hot Springs Foundation (LHSF) will administer the project according to the terms and conditions of the award including all applicable State regulations. The project will be funded by LHSF funds. The awarded contractor will receive instructions from LHSF. All site investigations shall be at not cost to the Owner.

DESCRIPTION OF PROJECT

Repair all minor structural damages in ride paths, prepare interior ride paths for gel coat, lay non-skid at start tubes if needed, re-caulk all seams, apply gel coat to a thickness of 18-24 mils., and wash, prime coat where needed, and paint exterior of the two slides listed below.

Slide A (Green slide) Enclosed slide
Enclosed Ride length - 138 feet
Run out- 38 feet
Diameter of slide – 32 inches
Total length for slide A - 176 feet

Slide B (Red slide) partial enclosure and partial open
Enclosed Ride length – 60 feet
Open Ride length – 144 feet (Note: inside circumference measures 5.5 feet)
Run out- 37 feet
Diameter of slide – 32 inches
Total length for slide B - 241 feet

Contractor will begin work at 195 N. Center Street, Lava Hot Springs, Idaho on or after September 12, 2022, to be completed on or before October 21, 2022, or as coordinated with the Agency contact.

RESPONSE

One (1) electronic PDF file of Exhibit A shall be emailed by the time specified above. **The email submittal shall clearly identify the point of contact regarding the submittal, with email, address and phone number listed.** Failure to identify point of contact may render submittal non-responsive.

AWARD

Based on the results of the submittals, a notice of intent to proceed will be issued to the lowest responsive bidder.

Exhibit A
RFQ0202101
Repair, Caulk, Paint and Gel Coat Waterslides
Price Sheet

This Price Sheet must be submitted with your quote.

Name of Vendor: _____

Provide your TOTAL COST for Repair, caulking, painting, and gel coat, meeting the specifications outlined. Your TOTAL COST must be fully burdened to include all costs associated with providing repair, caulking, painting, and gel coat meeting the required minimum specifications, including service at Lava Hot Springs Foundation at 195 N. Center, Lava Hot Springs, Idaho.

TOTAL COST for Project: \$ _____

or provide a cost structure/table for unit prices and extended prices, as appropriate

If awarded the contract, will you meet the timeline for completion specified in this RFQ?

YES__ *NO__

*A 'NO' response may disqualify you from consideration for award. If a longer delivery time is required, please provide an explanation:

Provide your approximate start date: _____

Company Name: _____

Contact Name/Phone: _____

Contact E-mail: _____